

MANDYA DIVISION, MANDYA.

Abstract Notification dated 15th May 1940.

The attention of the public is hereby invited to the notification, on pages 1157-1159, Part VI of the issue of the *Mysore Gazette*, dated 23rd May 1940, inviting tenders for the construction of a Trestle Bridge across Mosalehalli near Yannehole Village, Seringapatam Taluk.

The last date fixed for the receipt of tender in this office is 3rd June 1940.

B. S. NARASINGA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Notification dated 24th May 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 21st June 1940, for restoring Kasagar Chittkere (Major Tank) feeder to Jodikere Reg. No. 592, Thirthahalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga Division, between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury chellan for Rs. 190 credited to "17 (a) P. W. Deposits" in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Kasagar Chittkere (Major Tank) feeder to Jodikere Reg. No. 592, Thirthahalli Taluk, in default of which, tenders will be rejected."

5. The final acceptance of any tender will rest with the feeder who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy Brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposits.

Details of estimate for restoring Kasagar Chittkere (Major Tank) feeder to Jodikere Register No. 592, Tirthahalli Taluk.

Item No.	Description of work	Per	Rate	Quantity
	BUND R.L. 55.00 TOP WIDTH 6' SLOPES 2:1.			
1	Earthwork to bund with watering, tamping and consolidation	C.yds.	Rs. a. p. 0 6 0	103
2	Removing the temporary bund	"	0 3 0	62
3	Excavating for foundation in rocky soil at breach for using it for bund	"	0 8 0	4½
4	Cutting trenches in the bund and refilling with fresh earth with watering and consolidation for the front slope of bund to prevent percolation and leakage as the bund is a very old one	"	0 7 0	1,000

Item No.	Description of work	Per	Rate	Quantity
			Rs. a. p.	
5(a)	Size stone in surki mortar for core wall at breach	C.ft.	0 5 0	480
(b)	Puddle wall at the breach site	"	0 12 0	41
6	Constructing rough stone revetment at the breach	"	2 8 0	83
7	Turfing the slopes of bund both slopes	Sqr.	0 12 0	202
8	Watering and consolidation charges for the available earth used to bund	C.yd.	0 2 6	3,025
9	Providing and fixing grade stones including, figuring, painting, etc.	Each	2 8 0	5
10	Do Index stones	"	1 0 0	5
11	Do B. M. stones	"	4 0 0	2
12	Do Register No. and date stone	"	10 0 0	1
13	Providing iron gauge plates one at the sluice and the other at weir	"	10 0 0	2
SILT CLEARING IN THE TANK BED.				
1	Removal of silt from the tank bed	C.yd.	0 3 0	2,963
CONSTRUCTING A MASONRY WEIR 33 FT. LONG AT R.L. 50.00.				
1	Earthwork excavation in hard gravelly soil and using it to bund	C.yd.	0 4 0	178
2	Earthwork excavation in ordinary soil	"	0 3 6	92
3	Cement concrete 1 : 4 : 8 foundation of body wall	C.ft.	0 7 0	146
4	Size stone in cement mortar 1 : 5	"	0 8 0	275
5	Cement plastering	Sqr.	8 8 0	1 00
6	Cement pointing to exposed masonry	"	4 0 0	1 50
7	Rough stone work new	C.yd.	2 8 0	76
8	Jungle clearing	S.yd.	0 0 14	889
9	Unforeseen works	L. S.		
SLUICE AT R.L. 38.00.				
1	Cutting open the bund and refilling with watering and consolidation	C.yd.	0 6 0	107
2	Earthwork excavating foundation	"	0 4 0	10
3	Stone jelly concrete in cement mortar	C.ft.	0 7 0	136
4	Size stone in cement mortar	"	0 7 0	641
5	Stone jelly concrete in cement mortar 1 : 2 : 4	C.ft.	1 0 0	38
6	Cement pointing 1 : 3	Sqr.	4 0 0	1 50
7	Cement plastering 1 : 3 for cistern bed	"	8 8 0	0 50
8	Providing 6" diar. C.I. pipes of 12' long from Bhadravati	Each	20 0 0	5
9	Carting the pipes to site in 3 carts from Bhadravati	Mile	0 2 0	120
10	Fixing the pipes and cagging joint	Each	2 0 0	5
11	Burnt stone slabs 6" dressed and fixed	S.ft.	1 0 0	20
12	Providing one teak wood plug and iron rod with locking arrangement	L. S.	15 0 0	
13	Rough stone work new	C.yd.	2 8 0	60
14	Drilling holes in slabs	No.	1 0 0	2
15	Providing a jungle wood platform with slab support	L. S.		
16	Unforeseen items, clearing approach, etc.	"		
OTHER WORKS.				
1	Excavating check drain in hard soil and using sand for banking, etc.	C.yd.	0 4 0	700
2	Jungle clearing along bund and slopes	S.yd.	0 0 14	3,112

D. A. HUKERI,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 7th May 1940.

The attention of the public is invited to the notification for constructing Maternity Home at Hosdurga, published in the *Mysore Gazette*, dated 16th May 1940, Part VI on pages 1092-1095. The last date of the tender is 3rd June 1940.